



ALL LINTELS ARE TO BE
5.5"x9.5" GLULAM MATERIAL

Roof Plane Sheathing Area = 3105 sq. ft
 Gable Sheathing Area = 309 sq. ft
 Total Sheathing Area = 3415 sq. ft
 Fascia Material = 235 linear ft
 Ridge Cap Material = 77 linear ft

Total Truss Quantity = 39
 Heel Height = 12"
 Overhang = 20"
 Cantilever = 1 1/2"
 LSD Loading = 52.2 / 8.4

THIS DRAWING IS A PLACEMENT GUIDE ONLY.

CONFIRMATION OF ALL DIMENSIONS, QUANTITIES,
 LENGTHS & DETAILS REMAIN THE RESPONSIBILITY
 OF THE PERSON(S) INSTALLING THE ROOF SYSTEM.

ALL TRUSS DIMENSIONING IS TO THE CENTER,
 UNLESS STATED OTHERWISE.

GARDEN RIVER TRUSS CO. INC.

JOB LOCATION:

SALO RD., NAIRN CENTRE, ON

JOB DESCRIPTION:

FRED & JEANNE BROHART

DESIGNED BY:

MARC G. LEVASSEUR

JOB NO:
ML08218R

PAGE NO:
1 OF 1